BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No: EE/YNK/BBMP/E-PMT/20/2017-18 Dated: 23-02-2018

APPROVED TENDER SCHEDULE –'B'

Item No: 9

Name of Work:-Providing sign and ornamental boards in ward no 03

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri R S THYAGARAJ	
				Rate	Rate in Words
1	Providing and fixing ornamental name boards of size 2.10 X 0.50Mtrs and column of size 0.15 x 0.15 Mtrs of height 1.23 Mtrs of each board made of C C 1:1, 5:3 with necessary centrering and form work smooth finishing with reinforcement etc including fabrication charges painting concreting and transportation charges from manufacturing yard to the site of work all lead and lift loadiing and undloading and labour charges etc. complete as per the direction of the engineer incharge of the work	Each	10.00	6398.40	Rupees Six Thousand Three Hundred Ninety Eight and Paise Forty Only
2	Retro - Reflectorised Traffic Signs :- Providing and fixing of retro - reflectorised cautionary, mandatory and informatory sign as per IRC : 67 - 2001 made of high intensity grade micro prismatic HIP type IV sheeting, fixed over alumium sheeting, 2mm thick firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 45cms x 45cm x 60cm, 60 cm below ground level as per approved drawing. The item includes earthwork excavation, Cement Concrete M-15 grade, 2 coats of approved colour synthetic enamel painting to the steel surface, as per clauses, including curing, cost of all materials, labour, loading, unloading, lead, lift, transporting etc., complete.(P.No.65, I.No.8.04 of NH SR 2009-10) Supported on a class B GI pipe 80mm outer dia, 3.50mtr long 60cm x 60cm square	Each	160.00	5021.09	Rupees Five Thousand Twenty One and Paise Nine Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri R S THYAGARAJ	
				Rate	Rate in Words
3	KSRB 2-2.1 : Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(a) / 2.3.5, No.5/Item No. 2.3) SR 2016-17	Cum	2.16	206.75	Rupees Two Hundred Six and Paise Seventy Five Only
4	KSRB 100-1 Loading and unloading ofstone aggregates / sand/ kanker/ Moorum /soil KSRRB M100-1 Placing tipper at loading with front end loader dumpting turning for return trip excluding time for haulged and return trip complete as per specification item No 17.1 page 130 and KSRB M.100.4.1 costof haulage excluding loading and unloading MORTH to a distance of 4.00 K.M (Item No 17.4 Page 134 (SR 2016-17)	Cum	2.16	88.39	Rupees Eighty Eight and Paise Thirty Nine Only
5	KSRB-4-1.2 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement at 220kgs. with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.465cum machine mixed, concrete laid in layers not, exceeding 15cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 12/ Item No. 4.2/ PWD SR 2016-17	Cum	2.16	5519.92	Rupees Five Thousand Five Hundred Nineteen and Paise Ninety Two Only
6	KSRRB 800-1: painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specification MORTH chapter 8, No. 182/ Item No. 24.1/ PWD SR 2016-17	Sqm	52.80	65.64	Rupees Sixty Five and Paise Sixty Four Only

Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri R S THYAGARAJ	
			Rate	Rate in Words
KSRRB M800-9: Painting new Kannada letter and figures of any shade with synthetic enamel paint block or any other approved colour to give an even shade complete as per specification, ("ii) Hindi (Matras commas and the like not to be measured and paid for half letter shall be counted as half) MORTH specification No. 803, No. 184/ Item No. 24.9/ PWD SR 2016-17	Cum	58500.00	0.83	Rupees and Paise Eighty Three Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64

Executive Engineer
Yelahanka Division
Bruhat Bangalore Mahanagara Palike
BANGALORE 560064